


Sanford Underground Research Facility Tramway Rehabilitation Project Site Visit



Site Visit Agenda

Time	Topic	Presenter
9:00 – 9:05	Introductions	
9:05 – 9:15	Introduction to LBNF/DUNE	David Vardiman
9:15 – 9:30	Procurement Guidelines	Sharon Hemmingson
9:30 – 9:45	EH&S Requirements	John Emick
9:45 – 10:00	Tramway Rehabilitation Project Scope	David Vardiman
10:00 – 10:20	Site Specific Safety Training, video, waivers	John Emick
10:20 – 10:40	PPE, tag in, van ride to Round House Portal	D. Vardiman, J. Emick
10:40 – 11:00	Discussion on Round House Portal SOW	David Vardiman
11:00 – 11:10	Walk to North Portal	“ “
11:10 – 11:30	Discussion on North Portal SOW	“ “
11:30 – 11:40	Walk to Round House Portal	“ “
11:40 – 12:00	Communications Infrastructure SOW	“ “
12:00 – 12:15	Van ride to Yates Admin. building	D. Vardiman, J. Emick
12:15 – 12:30	Close Out	David Vardiman

Introduction to LBNF/DUNE Project

- The Deep Underground Neutrino Experiment will be a game-changing experiment for **neutrino science**, potentially transforming our understanding of why the universe exists as it does.
- The Long-Baseline Neutrino Facility is the infrastructure necessary to send a powerful beam of neutrinos 800 miles through the earth, and measure them deep underground at South Dakota's Sanford Underground Research Facility.
- The DUNE/LBNF project will be the first internationally conceived, constructed, and operated mega-science project hosted by the Department of Energy in the United States.


**LBNF will drive neutrino science forward the way
CERN's Large Hadron Collider drove Nobel Prize-
winning Higgs discovery**

LBNF/DUNE Project Overview

https://youtu.be/AYtKcZMJ_4c



Underground Context



4850 Level (4300 mwe)

Existing facilities

Proposed facilities

Far Site Scope – Timeline

1. Sanford Lab Reliability Projects

FY16 – 18

- Ross shaft rehab
- Hoist motor rebuilds, more...

2. Pre-Excavation


FY17 - 20

- Rock disposal systems
- Tramway rehab
- Headframe Reinforcement
- Conveyor System

3. Excavation/Construction

FY18 – 22


4. Cryostats/Cryogenic Systems *FY20 – 25*



Surface Waste Rock Handling

By eliminating rail transport and a transfer station we've:

- Avoided having to control noise and dust at the transfer point
- Reduced overall energy consumption
- Eliminated one of the more visible parts of the system, which would have been directly above Gold Run Park.
- Minimized people working in the tramway tunnel, thereby reducing potential for safety incidents.



Procurement

This slide presentation and today's Q&As will be posted online. To ensure fair and equitable competition, SDSTA uses a formal written Question & Answer process. *No information will be available to any prospective offeror outside of this Q&A process.*

Please review all of the contract requirements, particularly:

- ❖ Insurance (\$5M GL, \$2M PL; auto, WC, EL. Add'l insureds)
- ❖ Environmental Safety & Health
- ❖ Federal Requirements, including:
 - ❖ Registration in SAM.gov
 - ❖ E-verify
 - ❖ Davis-Bacon wage requirements
 - ❖ Buy American
 - ❖ Environmentally Preferable Products
- ❖ Release and Waivers (one per contract + one per person)
- ❖ Bond requirements
- ❖ Liquidated Damages – (Cost / \$100,000) x \$50 per day
- ❖ Submit resource-loaded schedule in Microsoft Project

Procurement

➤ [Price worksheet](#)
available on website

➤ Identify total cost per
scope of work deliverable

➤ Identify unit cost (per linear
foot) for 8 identified items

Cost Worksheet - SDSTA/SURF TRAMWAY REHABILITATION PROJECT		
Round House Portal Scope of Work	Total Cost	Cost per linear ft
Protection of existing infrastructure		
Razing of snowshed and existing portal		
Excavation to headwall and ground support		
Construction of new portal and gate		
Ballast		
Closure of old snowshed		
Reclamation		
Total	\$0	
North Portal Scope of Work	Total Cost	Cost per linear ft
Protection of existing infrastructure		
Razing of snowshed and existing portal		
Excavation to headwall and ground support		
Construction of new portal and gate		
Ballast		
Rebuild snowshed connection		
Reclamation		
Total	\$0	
Communication Infrastructure Relocation	Total Cost	
Installation of new conduit connections to existing conduit		
Installation of new fiber optic and Femco lines		
Total	\$0	
Mobilization/demobilization		
Fixed Price	\$0	

Contractor EH&S Requirements


- Contractor is expected to obey all OSHA Construction Safety Regulations found in 29 CFR 1926 and Sanford Laboratory's Construction Safety Manual (see website)
- Contractor will have a dedicated ES&H representative on site ensuring all health, safety and environmental requirements of the work will be met (i.e. hot-work, hoisting and rigging, fall protection, confined space, injury reporting, site security, current and appropriate training)
- Contractor and employees will use a 5-point card
- Contractor will document all employee safety training records
- Daily toolbox talks will start each shift. Choose a topic that fits for the day and discuss issues that could become unsafe practices. The talks must be documented and available for inspection
- Job Hazard Analyses will be required for work that involves lifts, confined space, Contractor will use Sanford Laboratory's JHA form found in the website
- Weekly meetings with the Project Managers to provide updates to schedules, coordination reviews, traffic, and pedestrian paths. Meet in the Administration building, day/times TBD
- Contractor will ensure all workers receive Sanford Laboratory's site specific training
- The contractor will provide a quality assurance plan. Contractor will have a site security plan and means to restrict access and control site entry without permission

Tramway Rehabilitation Project Work Schedule

The expected schedule, subject to change, is as follows:

Proposals due to SDSTA	April 3, 2017
Successful Offeror Selected	May 1, 2017
Owner/Contractor/Designer Value Engineering	May 8, 2017
Updated Proposals following VE	May 12, 2017
Contract Issued	May 15, 2017
NTP Issued	Aug 1, 2017
<i>CM/GC Mobilizes</i>	<i>Jan 31, 2018</i>
Contract Ends	May 15, 2018

Tramway Rehabilitation Project Overview



Contract Technical Scope

Round House Portal

- Protection of existing infrastructure**
- Razing of snowshed and existing portal**
- Excavation to headwall and ground support**
- Construction of new portal and gate**
- Ballast**
- Closure of old snowshed**
- Reclamation**

North Portal

- Protection of existing infrastructure**
- Razing of snowshed and existing portal**
- Excavation to headwall and ground support**
- Construction of new portal and gate**
- Ballast**
- Rebuild snowshed connection**
- Reclamation**


Communications Infrastructure Relocation

- Installation of new conduit connections to existing conduit**
- Installation of new fiber optic and Femco lines**


Round House Portal



Round House Portal





North Portal



NOTES:

- FOR GENERAL NOTES, SEE DWG PER-E-C-002.
- REMOVE DEBRIS ON TOP OF EXISTING TIMBER POSTS OUTSIDE THE TUNNEL AND CLEAN THE AREA.
- REPLACE ROOF AND JOISTS OF THE OLD SNOWSHED FROM APPROXIMATELY STA. 14+10 TO THE NEW PORTAL TO MATCH WITH THE REST OF THE SNOWSHED.
- FOLLOW SEQUENCE BELOW FOR THE PORTAL REFURBISHMENT:
 - REMOVE TIMBER LAGGING AND TIMBER POSTS IN TUNNEL ONE AT A TIME AND REPLACE WITH PATTERN BOLTING AND MESH.
 - REMOVE TIMBER POSTS AND LAGGING AT THE PORTAL OUTSIDE THE TUNNEL.
 - REMOVE LOOSE GROUND AT THE CROWN AND SIDES OF THE TUNNEL PORTAL TO REACH COMPETENT GROUND.
 - INSTALL BOLTS AND MESH AROUND TUNNEL PORTAL AS SHOWN IN SECTION. APPLY 2" OF SHOTCRETE IF REQUIRED.
 - INSTALL 0.2" (5mm) THICK LINER PLATE TO FORM AN 8'-0" WIDE AND 7'-0" HIGH HORSE-SHOE TUNNEL FROM THE END OF SNOWSHED (APPROX. STA. 14+65) TO MIN 3'-0" INSIDE THE TUNNEL (APPROX. STA. 14+85).
 - FORM AROUND THE LINER PLATE AND POUR CAST-IN-PLACE CONCRETE WITH MIN 2'-0" COVER ALL AROUND.



		ARUP Arup USA Inc. 77 Water Street, New York NY 10005, T 212 666 3000 www.arup.com	
		McMILLEN JACOBS srk consulting ASSOCIATES MINCORE	
REV	DATE	DESCRIPTION	
4	12/23/16	PRE-EXCAVATION 100% FINAL DESIGN SUBMISSION	
3	10/13/16	PRE-EXCAVATION 80% FINAL DESIGN SUBMISSION	
2	07/14/16	PRE-EXCAVATION 60% FINAL DESIGN SUBMISSION	
1	03/22/16	PRE-EXCAVATION 30% FINAL DESIGN SUBMISSION	

SCALE:

AS NOTED



Long-Baseline Neutrino Facility

DESIGNED	AG	ARUP
DRAWN	NK	ARUP
CHECKED	JH	ARUP


LBNF-FSCF-EXCAVATION PRE EXCAVATION PACKAGE TRAMWAY TUNNEL REHABILITATION NORTH PORTAL SUPPORT

DRAWING NO. **15-1-6** **PER-E-C-982** REV. **4**

Section at North
Portal Looking East
Towards Round
House Portal

North Wall

South Wall




TYPICAL CROSS SECTION AT TRAMWAY SUPPORT

SCALE: 1" = 1'-0"

1

[illegible]

Portal Gates Design & Fabrication



* ABSOLUTE MINIMUM CLEARANCE 0'-9" AT LOCATIONS WITH REDUCED WIDTH SHOWN ON DWGS PER-E-C-964 TO PER-E-C-969

**ABSOLUTE MINIMUM CLEARANCE 3'-3" AT LOCATIONS WITH REDUCED WIDTH SHOWN ON DWGS PER-E-C-964 TO PER-E-C-969

SECTION ON TRAMWAY CLEARANCE

SCALE: 1/2" = 1'-0"


Communication Infrastructure Relocation

GENERAL NOTES: SITE PLAN

- A. SEE PER-B-T-301 FOR RACEWAY SINGLE LINE DIAGRAM.
- B. SEE PER-B-T-302 FOR CABLE/STRAND COUNT DETAILS.
- C. PROVIDE FULL BOXES AS NEEDED FOR ALL RACEWAYS.

KEY NOTES: SITE PLAN

- 1. CABLE TRANSITION FROM YATES TRAMWAY INTO YATES SHAFT. CABLES TO BE ROUTED EXPOSED WITH CONTINUOUS SUPPORT DOWN SHAFT.
- 2. THREE EXISTING 4" CONDUITS TO BE USED FOR ROUTING OF NEW FIBER.
- 3. APPROXIMATE ROUTE OF FIBER RUNS WITHIN ROSS TRAMWAY AND YATES TRAMWAY.
- 4. ONE NEW 4" CONDUIT TO BE INSTALLED IN EXISTING UNDERGROUND WALK-THROUGH TUNNEL FROM HEADFRAME TO EDUCATION AND OUTREACH BUILDING.
- 5. APPROXIMATE FIBER ROUTE IN EXISTING UTILITY CHASE FROM EDUCATION AND OUTREACH BUILDING TO YATES ADMIN BUILDING.



REV	DATE	DESCRIPTION
5	12/23/16	PRE-EXCAVATION 100% FINAL DESIGN SUBMISSION
4	11/03/16	PRE-EXCAVATION 90% FINAL DESIGN REV. A SUBMISSION
3	10/13/16	PRE-EXCAVATION 90% FINAL DESIGN SUBMISSION
2	07/14/16	PRE-EXCAVATION 60% FINAL DESIGN SUBMISSION
1	03/23/16	PRE-EXCAVATION 30% FINAL DESIGN SUBMISSION


ARUP
ARUP USA Inc.
77 Water Street, New York NY 10005, T 212 896 3000
www.arup.com

TSP Inc.
851 Kameo Dr SE
Renton WA 98057
Phone: (855) 944-1432
Fax: (855) 943-1109
www.tspinc.com

TSP

srk consulting

POWER ENGINEERS



Fermilab
Long-Baseline Neutrino Facility

DESIGNED	DLB	TSP
DRAWN	KAO	TSP
CHECKED	DLB	TSP

LBNF • FSCF • BSI
PRE-EXCAVATION PACKAGE
CYBERINFRASTRUCTURE
ENLARGED SITE PLAN - YATES COMPLEX

DRAWING NO. **15-1-6** **PER-B-T-103** REV. **5**

Questions?