

SDSTA is issuing an amendment to the subject RFP to incorporate an updated set of design drawings, as discussed during the Site Visit. Revisions are identified in the drawings with revision clouds marked with a “2” inside a triangle. The updates reflect an increase in the number of feeders from the new Yates Crusher Substation switchgear to the Yates Hoist Building basement, from one feeder to three. All three feeder cable ends shall be coiled in the Yates Hoist Building basement for future connection by the electrical contractor performing the Yates Hoist Upgrades.

Because this change results in no remaining spare breakers in the new switchgear, the Yates Crusher Substation layout has been adjusted to provide space for an additional switchgear section to be added in the future by others.

This amendment also extends the “Questions Due” milestone to March 10th and the “Questions and Answers Posted” milestone to March 12th. The proposal due date remains March 26th. If additional time is required to finalize a proposal, please submit a request for an extension. All other provisions of the RFP remain unchanged.

This Amendment is effective March 5, 2026.