

Questions/Answers

RFB – Asbestos Ross Substation Trestle

- 1) **Background asbestos minerals that do not come from the friable pipe asbestos?** SURF will provide background readings that will provide a means of comparison.
- 2) **Grubbing & Trees?** Removal or trimming to get to site is contractor's responsibility, yes may have to come in with smaller equipment.
- 3) **Is contractor responsible for backfilling?** Yes
- 4) **Is contractor responsible to reseed?** No
- 5) **Trestle work off lifts or scaffolding?** The contractor may use both methods provided that work complies with the OSHA general industry standard for fall protection.
- 6) **Contractor can stream trim brushes?** Yes, if we don't have to disturb the soil then don't
- 7) **Brush removal?** It is the contractor's responsibility to manage the brush to provide access and inspection of the ground. It is better to trim the brush than remove it completely unless the bottom of the brush is in the way.
- 8) **Recommendation for weed eating site?** Contractor will need to pick up debris before you weed eat.
- 9) **Can we tie off red iron on the trestle?** If a qualified and competent person (engineer) so documents (5000 lbs. minimum). It is the contractor's responsibility to have a fall protection plan and verify all tie-off points meet OSHA requirements.
- 10) **Is the width the same on the entire trestle?** To the best of our knowledge it is.
- 11) **Is there Power and water access?** This is up to the contractor to provide that as there is no power or water nearby.