

Attachment H - Specifications

SDSTA DIVISION ONE GUIDE SPECIFICATION

TABLE OF CONTENTS

SUMMARY OF WORK	2
ADMINISTRATIVE REQUIREMENTS	4
PROJECT CONSTRUCTION PROGRESS SCHEDULES	6
SUBMITTAL PROCEDURES	8
QUALITY CONTROL FOR CONSTRUCTION	13
TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS	18
CLOSEOUT SUBMITTALS	22
OPERATION AND MAINTENANCE DATA	24

SUMMARY OF WORK**Part 1 General****1.1 WORK COVERED BY CONTRACT DOCUMENTS****1.1.1 Project Description**

The work includes the following items:

- Tying into existing below grade 24" discharge piping at the RBC channel with a new 20" HDPE line including all valving and valve boxes.
- Installation of approximately 120 ft of below grade 20" HDPE line that connects the RBC channel discharge to the discharge piping off the cooling reservoir.
- All trenching and backfilling.
- Installation of a bypass around the Yardney filter pumps includes the purchase and installation of an electric keystone modulating valve and card with Victaulic adapter.
- Replacing approximately 50 ft of corroded 12" piping in the sand filter building (building entrance to sand filter entrance).
- All materials and supplies and all incidental related work.

1.1.2 Location

The work is located at the Sanford Underground Research Facility, approximately as indicated with all work taking place at the Wastewater Treatment Plant in the area around the RBC discharge and sand filter building.

1.2 OCCUPANCY OF PREMISES

Building/location of work will be occupied during performance of work under this Contract. Occupancy notifications will be posted in a prominent location in the work area.

Before work is started, coordinate with the Project Manager to arrange a sequence of procedure, means of access, space for storage of materials and equipment, and use of approaches, corridors, and stairways.

1.3 EXISTING WORK

Remove or alter existing work in such a manner as to prevent injury or damage to any portions of the existing work which remain. Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as approved by the Project Manager. At the completion of operations, existing work must be in a condition equal to or better than that which existed before new work started.

1.4 LOCATION OF EXISTING UTILITIES

Obtain digging permits prior to start of excavation and comply with facility requirements for locating and marking underground utilities. Contact local utility locating service a minimum of 72 hours prior to

excavating, to mark utilities, and within sufficient time required if work occurs on a Monday or after a holiday. Verify existing utility locations indicated on contract drawings, within area of work.

1.4.1 Notification Prior to Excavation

Notify the Project Manager at least 5 days prior to starting excavation work.

--- End of Section ---

ADMINISTRATIVE REQUIREMENTS**Part 1 General****1.1 PROGRESS AND COMPLETION PICTURES**

Photographically document site conditions prior to start of construction operations. Provide monthly digital photographs showing the sequence and progress of work to clearly capture the work performed during that period, in particular areas that will be covered as part of the scope of work. Submit with the monthly invoice. Photographs provided are for unrestricted use by the SDSTA.

1.2 SUPERVISION**1.2.1 Minimum Requirements**

Have at least one qualified superintendent, or competent alternate, capable of reading, writing, and conversing fluently in the English language, on the job-site at all times during the performance of contract work.

1.2.2 Superintendent Qualifications

The project superintendent must have a minimum of 10 years' experience in construction with at least 2 of those years as a superintendent on projects similar in size and complexity. The individual must have experience in the areas of hazard identification and safety compliance. The individual must be capable of interpreting a critical path schedule and construction drawings. The qualification requirements for the alternate superintendent are the same as for the project superintendent. The Contracting Officer may request proof of the superintendent's qualifications at any point in the project if the performance of the superintendent is in question.

For routine projects where the superintendent is permitted to also serve as the Quality Control (QC) Manager as established in Section QUALITY CONTROL, the superintendent must have qualifications in accordance with that section.

1.2.2.1 Duties

The project superintendent is primarily responsible for managing and coordinating day-to-day production and schedule adherence on the project. The superintendent is required to attend status meetings and quality control meetings if applicable. The superintendent or qualified alternate must be on-site at all times during the performance of this contract until the work is completed and accepted.

1.2.3 Non-Compliance Actions

The project superintendent is subject to removal by the Contracting Officer for non-compliance with requirements specified in the contract and for failure to manage the project to insure timely completion. Furthermore, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders is acceptable as the

subject of claim for extension of time for excess costs or damages by the Contractor.

1.3 PRECONSTRUCTION CONFERENCE

After award of the contract but prior to commencement of any work at the site, meet with the Project Manager to discuss and develop a mutual understanding relative to the administration of the quality control, safety program, preparation of the schedule of prices, shop drawings, and other submittals, scheduling programming, and prosecution of the work. Major subcontractors who will engage in the work must also attend.

--- End of Section ---

PROJECT CONSTRUCTION PROGRESS SCHEDULES**Part 1 General****1.1 SUBMITTALS**

Construction Schedule

Monthly Schedule Updates

1.2 ACCEPTANCE

Prior to the start of work, prepare and submit a construction schedule in the form of a bar chart schedule to the Project Manager for acceptance

The acceptance of a baseline construction schedule is a condition precedent to:

- a. Starting work on the demolition or construction stage(s) of the contract.
- b. Processing Contractor's invoice(s) for construction activities.
- c. Review of any schedule updates.

Submittal of the baseline schedule, and subsequent schedule updates, is understood to be the Contractor's certification that the submitted schedule meets all of the requirements of the contract documents, represents the Contractor's plan on how the work will be accomplished, and accurately reflects the work that has been accomplished and how it was sequenced.

1.3 SCHEDULE FORMAT**1.3.1 Bar Chart Schedule**

The bar chart must, as a minimum, show work activities, major material/equipment delivery, on-site construction, key inspections, and closeout activities. The bar chart must be time scaled and generated using an electronic spreadsheet program.

1.3.2 Schedule Submittals and Procedures

Submit a bar chart schedule and updates in hard copy and in an electronic format that is acceptable to the Project Manager.

1.4 SCHEDULE MONTHLY UPDATES

Update the construction schedule at monthly intervals or when the schedule has been revised. The updated schedule must be kept current, reflecting actual progress and plan for completing the remaining work.

1.5 CONTRACT MODIFICATION

Submit a schedule analysis with each cost and time proposal for a proposed change. The analysis must illustrate the influence of each change or delay on the contract completion date or milestones. No time extensions will be granted nor delay damages paid unless a delay occurs which consumes all available project float and extends the projected

finish beyond the contract completion date. Identify types of delays as follows:

(a) Excusable Delay: Force-Majeure (e.g. unusual weather) - Contractor may receive time extension, but time will not be compensable.

(b) Inexcusable Delay: Contractor Responsibility - Contractor will not receive time extension.

(c) Compensable Delay: SDSTA Responsibility - Contractor may receive compensable time extension.

If a combination of any of the delay types outlined above occurs, it is considered a Concurrent Delay, which will require an analysis of the facts to determine compensability and entitlement to any time extension under the applicable contract clauses.

1.6 WEEKLY PROJECT STATUS MEETING AND 3-WEEK LOOK AHEAD SCHEDULE

Each week during the active construction period, a Weekly Status Meeting will be held. At a minimum, the project superintendent should attend representing the Contractor. Meeting minutes will be taken by the superintendent or other designated rep to capture the discussions. As part of the process, the Contractor will prepare and issue a 3-Week Look Ahead schedule to provide a more detailed day-to-day plan of upcoming work identified on the construction schedule. Additionally, include upcoming outages, closures, etc. The detailed work plans are to be bar chart schedules, separate from the construction schedule on an electronic spreadsheet program and printed on (8-1/2 by 11 inch) sheets as directed by the Project Manager. In addition to schedule discussions, the Weekly Status Meeting should discuss status of submittal reviews and approvals, Requests for Information (RFIs), outstanding change orders, and other relevant project coordination issues.

--- End of Section ---

SUBMITTAL PROCEDURES**Part 1 General****1.1 DEFINITIONS****1.1.1 Submittal Descriptions (SD)**

Submittal requirements in addition to those noted below may be specified in the technical spec sections and drawings.

Preconstruction Submittals

Submittals which are required prior to start of construction (work). These submittals are considered Action Submittals (See definition below).

- List of Proposed Subcontractors
- Construction Progress Schedule
- Submittal Register
- Schedule of Prices
- Health and Safety Plan
- Quality Control (QC) Plan
- Environmental Protection Plan

Product Data

Catalog cuts, illustrations, schedules, diagrams, performance charts, instructions and brochures illustrating size, physical appearance and other characteristics of materials, systems, or equipment for some portion of the work.

Samples of warranty language when the contract requires extended product warranties.

Samples

Fabricated or unfabricated physical examples of materials, equipment or workmanship that illustrate functional and aesthetic characteristics of a material or product and establish standards by which the work can be judged.

Color samples from the manufacturer's standard line (or custom color samples if specified) to be used in selecting or approving colors for the project.

Field samples and mock-ups constructed on the project site establish standards by which the ensuring work can be judged. Includes assemblies or portions of assemblies which are to be incorporated into the project and those which will be removed at conclusion of the work.

Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified

requirements. Unless specified in another section, testing must have been within three years of date of contract award for the project.

Report which includes findings of a test required to be performed by the Contractor on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report which includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Certificates

Statements printed on the manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that the product, system, or material meets specification requirements. Must be dated after award of project contract and clearly name the project.

Operation and Maintenance Data

Data that is furnished by the manufacturer, or the system provider, to the equipment operating and maintenance personnel, including manufacturer's help and product line documentation necessary to maintain and install equipment. This data is needed by operating and maintenance personnel for the safe and efficient operation, maintenance, and repair of the item.

This data is intended to be incorporated in an operations and maintenance manual or control system.

Closeout Submittals

Documentation to record compliance with technical or administrative requirements or to establish an administrative mechanism.

Special requirements necessary to properly close out a construction contract. For example, as-built drawings. Also, submittal requirements necessary to properly close out a major phase of construction on a multi-phase contract.

1.2 SUBMITTAL REGISTER

1.2.1 Use of Submittal Register

Submit a register of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or revisions to submittals and additional time for handling and reviewing submittals required by those corrections.

Coordinate submittal register with list of subcontracts, the schedule of values, and Contractor's construction schedule.

Initial Submittal. Submit concurrently with startup construction schedule. Include submittals required during the first 60 days of construction. List those submittals required to maintain orderly

progress of the Work and those required early because of long lead time for manufacture or fabrication.

Submit revised submittal schedule to reflect changes in current status and timing for submittals.

Format. Arrange the following information in a tabular format. (As applicable)

- a. Scheduled date for first submittal.
- b. Specification/RFP Section number and title.
- c. Submittal category: Action; informational.
- d. Name of subcontractor.
- e. Description of the Work covered.
- f. Scheduled date for final release or approval.
- g. Scheduled date of fabrication.
- h. Scheduled dates for purchasing.
- i. Scheduled dates for installation.
- j. Activity or event number.

1.3 VARIATIONS

Variations from contract requirements require SDSTA approval and will be considered where advantageous to SDSTA.

1.3.1 Considering Variations

Discussion with Project Manager prior to submission will help ensure functional and quality requirements are met and minimize rejections and re-submittals.

Specifically point out variations from contract requirements in transmittal letters. Failure to point out deviations may result in the rejection and removal of such work at no additional cost to the SDSTA.

1.3.2 Proposing Variations

When proposing variation, deliver written request to the Project Manager, with documentation of the nature and features of the variation and why the variation is desirable and beneficial to SDSTA. If lower cost is a benefit, also include an estimate of the cost savings. In addition to documentation required for variation, include the submittals required for the item. Clearly mark the proposed variation in all documentation.

1.3.3 Warranting that Variations are Compatible

When delivering a variation for approval, Contractor warrants that this contract has been reviewed to establish that the variation, if incorporated, will be compatible with other elements of work.

1.3.4 Review Schedule Extension

In addition to normal submittal review period, a period of 10 working days will be allowed for consideration by SDSTA of submittals with variations.

1.4 SCHEDULING

Schedule and concurrently submit submittals covering component items forming a system or items that are interrelated. Include certifications to be submitted with the pertinent drawings at the same time. No delay damages or time extensions will be allowed for time lost in late submittals.

- a. Coordinate scheduling, sequencing, preparing, and processing of submittals with performance of work so that work will not be delayed by submittal processing. Allow for potential resubmittal of requirements.
- b. Re-submit register and annotate monthly by the Contractor with actual submission and approval dates. When all items on the register have been fully approved, no further re-submittal is required.
- c. Carefully control procurement operations to ensure that each individual submittal is made on or before the Contractor scheduled submittal date shown on the approved "Submittal Register."

1.4.1 Review Notations

Submittals will be returned to the Contractor with the following notations:

- a. Submittals marked "accepted" authorize the Contractor to proceed with the work covered.
- b. Submittals marked "accepted as noted" or "accepted as noted, resubmittal not required," authorize the Contractor to proceed with the work covered provided he takes no exception to the corrections.
- c. Submittals marked "revise and resubmit," indicate noncompliance with the contract requirements or design concept, or that submittal is incomplete. Resubmit with appropriate changes. No work shall proceed for this item until resubmittal is approved.
- d. Submittals marked "not reviewed" will indicate submittal has been previously reviewed and accepted, is not required, does not have evidence of being reviewed and approved by Contractor, or is not complete. A submittal marked "not reviewed" will be returned with an explanation of the reason it is not reviewed. Resubmit submittals returned for lack of review by Contractor or for being incomplete, with appropriate action, coordination, or change.

1.5 REJECTED SUBMITTALS

If the Contractor considers any correction or notation on the returned submittals to constitute a change to the contract drawings or specifications; notice as required under the contract is to be given to the Contracting Officer. Contractor is responsible for the dimensions and design of connection details and construction of work. Failure to point out deviations may result in the SDSTA requiring rejection and removal of such work at the Contractor's expense.

If changes are necessary to submittals, make such revisions and submission of the submittals in accordance with the procedures above. No item of work requiring a submittal change is to be accomplished until the changed submittals are approved.

1.6 ACCEPTED SUBMITTALS

The acceptance of submittals is not to be construed as a complete check and indicates only that acceptance will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor under the Contractor Quality Control (CQC) requirements of this contract is responsible for dimensions, the design of adequate connections and details, and the satisfactory construction of all work.

After submittals have been accepted, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.7 APPROVED SAMPLES

Approval of a sample is only for the characteristics or use named in such approval and is not be construed to change or modify any contract requirements. Before submitting samples, the Contractor is to assure that the materials or equipment will be available in quantities required in the project. No change or substitution will be permitted after a sample has been approved.

Match the approved samples for materials and equipment incorporated in the work. If requested, approved samples, including those which may be damaged in testing, will be returned to the Contractor, at his expense, upon completion of the contract.

Samples of various materials or equipment delivered on the site or in place may be taken by the SDSTA for testing. Samples failing to meet contract requirements will automatically void previous approvals. Contractor to replace such materials or equipment to meet contract requirements.

Approval of the Contractor's samples does not relieve the Contractor of his responsibilities under the contract.

--- End of Section ---

QUALITY CONTROL FOR CONSTRUCTION**Part 1 General****1.1 SUBMITTALS**

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

QC Plan;

Submit a QC Plan within 15 calendar days after receipt of Notice of Award.

1.2 INFORMATION REQUIREMENTS

Prior to commencing work on construction, the Contractor can obtain a single copy set of the current report forms from the Project Manager. The report forms will consist of the Contractor DAILY Report, Contractor DAILY Report (Continuation Sheet), Rework Items List, and Testing Plan and Log.

Deliver the following to the Project Manager and the designated SDSTA QA Rep:

- a. DAILY Report: By 10:00 AM the next working day after each day that work is performed;
- b. Field Test Reports: One copy, within one week after the test is performed, attached to the CQC Report;
- c. QC Certifications: As required by the paragraph entitled "QC Certifications."

1.3 QC PROGRAM REQUIREMENTS

Establish and maintain a QC program as described in this section. The QC program consists of a QC Manager, a QC Plan, a Project Preconstruction Conference, Weekly Status Meeting, submittal review, testing, and QC certifications and documentation necessary to provide materials, equipment, workmanship, fabrication, construction, and operations which comply with the requirements of this contract. The QC program shall cover on-site and off-site work and shall be keyed to the work sequence. No work or testing may be performed unless the QC Manager is on the work site.

1.3.1 Preliminary Work Authorized Prior to Acceptance

The only work that is authorized to proceed prior to the acceptance of the QC Plan is mobilization of storage and office trailers, temporary utilities, and surveying.

1.3.2 Acceptance

Acceptance of the QC Plan is required prior to the start of construction. SDSTA reserves the right to require changes in the QC Plan and operations as necessary, including removal of personnel, to ensure the specified quality of work.

1.3.3 Notification of Changes

Notify the Contracting Officer, in writing, of any proposed change, including changes in the QC organization personnel, a minimum of seven calendar days prior to a proposed change. Proposed changes shall be subject to the acceptance by the Contracting Officer.

1.4 QC ORGANIZATION

1.4.1 QC Manager

1.4.1.1 Duties

Provide a QC Manager at the work site to implement and manage the QC program. In addition to implementing and managing the QC program, the QC Manager may perform the duties of project superintendent. The QC Manager is required to attend the Project Preconstruction Meeting, conduct the QC meetings (if separate from the Weekly Status Meeting), perform submittal review, ensure testing is performed and provide QC certifications and documentation required in this contract. The QC Manager is responsible for managing and coordinating documentation performed by others.

1.4.1.2 Qualifications

An individual with a minimum of 10 years combined experience as a superintendent, inspector, QC Manager, project manager, or construction manager on similar size and type construction contracts which included the major trades that are part of this contract. The individual must be familiar with and have experience in the areas of hazard identification and safety compliance.

1.4.2 Alternate QC Manager Duties and Qualifications

Designate an alternate for the QC Manager to serve in the event of the designated QC Manager's absence. The period of absence may not exceed two weeks at one time, and not more than 30 workdays during a calendar year. The qualification requirements for the Alternate QC Manager shall be the same as for the QC Manager.

1.5 QC PLAN

1.5.1 Requirements

Provide, for acceptance by the Contracting Officer, a QC Plan that covers both on-site and off-site work and includes the following with a table of contents listing the major sections identified with tabs.

I. QC ORGANIZATION: A chart showing the QC organizational structure and its relationship to the production side of the organization.

II. NAMES AND QUALIFICATIONS: In resume format, for each person in the QC organization.

III. DUTIES, RESPONSIBILITY AND AUTHORITY OF QC PERSONNEL: Of each person in the QC organization.

IV. OUTSIDE ORGANIZATIONS: A listing of outside organizations such as architectural and consulting engineering firms that will be employed by the Contractor and a description of the services these firms will provide.

V. APPOINTMENT LETTERS: Letters signed by an officer of the firm appointing the QC Manager and Alternate QC Manager and stating that they are responsible for managing and implementing the QC program as described in this contract. Include in this letter the QC Manager's authority to direct the removal and replacement of non-conforming work.

VI. SUBMITTAL PROCEDURES AND INITIAL SUBMITTAL REGISTER: Procedures for reviewing and managing submittals. Provide the name(s) of the person(s) in the QC organization authorized to review and certify submittals prior to approval.

VII. TESTING LABORATORY INFORMATION: Testing laboratory information required by the paragraphs "Accredited Laboratories" or "Testing Laboratory Requirements", as applicable.

VIII. TESTING PLAN AND LOG: A Testing Plan and Log that includes the tests required, referenced by the specification paragraph number requiring the test, the frequency, and the person responsible for each test.

IX. PROCEDURES TO COMPLETE REWORK ITEMS: Procedures to identify, record, track and complete rework items.

X. DOCUMENTATION PROCEDURES: Use SDSTA formats or agreed upon formats with SDSTA QA Manager and Contractor.

XI. PROCEDURES FOR COMPLETION INSPECTION: See the paragraph entitled "COMPLETION INSPECTIONS".

1.6 PROJECT PRECONSTRUCTION CONFERENCE

During the Preconstruction Conference and prior to the start of construction, discuss the QC program required by this contract. The purpose is to develop a mutual understanding of the QC details, including documentation, administration for on-site and off-site work, and the coordination of the Contractor's management, production, and QC personnel. At the meeting, the Contractor will be required to explain how quality control will be implemented for key features of work. Contractor's personnel required to attend shall include the QC Manager, project manager, and superintendent. Minutes of the meeting will be prepared by the QC Manager and signed by both the Contractor and the Project Manager. The Contractor shall provide a copy of the signed minutes to all attendees.

1.7 QC CERTIFICATIONS (AL, SAMPLING AND TESTING? NOT REQUIRED?)

1.7.1 Invoice Certification

Furnish a certificate with each payment request, signed by the QC Manager, attesting that as-built drawings are current and attesting that the work for which payment is requested, including stored material is in compliance with contract requirements.

1.7.2 Completion Certification

Upon completion of work under this contract, the QC Manager shall furnish a certificate attesting that "the work has been completed, inspected, tested and is in compliance with the contract."

1.8 COMPLETION INSPECTIONS

1.8.1 Punch-Out Inspection

Near the completion of all work or stated elsewhere in the specifications, the QC Manager shall conduct an inspection of the work and develop a punch list of items which do not conform to the approved drawings and specifications. Include in the punch list any remaining items of the "Rework Items List", which were not corrected prior to the Punch-Out inspection. The punch list shall include the estimated date by which the deficiencies will be corrected. A copy of the punch list shall be provided to the Project Manager. The QC Manager or staff shall make follow-on inspections to ascertain that all deficiencies have been corrected. Once this is accomplished, the Contractor shall notify the SDSTA that the facility is ready for the SDSTA "Pre-Final Inspection".

1.8.2 Pre-Final Inspection

The SDSTA and QC manager will perform this inspection to verify that the facility is complete and ready to be occupied. A SDSTA pre-final punch list may be developed as a result of this inspection. The QC Manager shall ensure that all items on this list are corrected prior to notifying the SDSTA that a "Final" inspection with the customer can be scheduled. Any items noted on the "Pre-Final" inspection shall be corrected in a timely manner and shall be accomplished before the contract completion date for the work or any particular increment thereof if the project is divided into increments by separate completion dates.

1.8.3 Final Acceptance Inspection

The QC Manager, the superintendent, or other Contractor management personnel and the Project Manager and SDSTA QA Rep will be in attendance at this inspection. The final acceptance inspection will be formally scheduled based upon results of the "Pre-Final Inspection".

1.9 DOCUMENTATION

Maintain current and complete records of on-site and off-site QC program operations and activities. Reports are required for each day work is performed. Account for each calendar day throughout the life of the contract. The superintendent and the QC Manager (If separate) must prepare and sign the Contractor DAILY Report. The reporting of work shall be identified by terminology consistent with the construction schedule. Use the "remarks" section in this report to record pertinent information including directions received, problems encountered during construction, work progress and delays, conflicts or errors in the drawings or specifications, field changes, safety hazards encountered, instructions given and corrective actions taken, delays encountered and a record of visitors to the work site.

1.9.1 As-Built Drawings

The QC Manager is required to review the as-built drawings and ensure they are kept current on a regular basis and marked to show deviations, which have been made from the Contract drawings. Ensure each deviation

has been identified with the appropriate modifying documentation, e.g. modification number, RFI number, etc. The QC Manager shall initial each deviation or revision. Upon completion of work, the QC Manager shall submit a certificate attesting to the accuracy of the as-built drawings prior to submission to the SDSTA.

1.10 NOTIFICATION ON NON-COMPLIANCE

The Project Manager or QA Rep will notify the Contractor of any detected non-compliance with the foregoing requirements. The Contractor shall take immediate corrective action. If the Contractor fails or refuses to correct the non-compliant work, the Contracting Officer will issue a non-compliance notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. The Contractor shall make no part of the time lost due to such stop orders the subject of claim for extension of time, for excess costs, or damages.

--- End of Section ---

TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS**Part 1 General****1.1 REFERENCES**

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C511 (2007) Standard for Reduced-Pressure Principle Backflow Prevention Assembly

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 241 (2015) Standard for Safeguarding Construction, Alteration, and Demolition Operations

NFPA 70 (2017) National Electrical Code

1.2 SUBMITTALS

Submit the following in accordance with Section SUBMITTAL PROCEDURES:

Construction Site Plan

1.3 CONSTRUCTION SITE PLAN

Prior to the start of work, submit a site plan showing the locations and dimensions of temporary facilities (including layouts and details, equipment and material storage area (onsite and offsite), and access and haul routes, avenues of ingress/egress to the fenced area and details of the fence installation. Identify any areas which may have to be graveled to prevent the tracking of mud. Indicate if the use of a supplemental or other staging area is desired. Show locations of safety and construction fences, site trailers, construction entrances, trash dumpsters, temporary sanitary facilities, and worker parking areas.

Part 2 Products**2.1 TEMPORARY TRAFFIC CONTROL****2.1.1 Haul Roads**

Construct access and haul roads necessary for proper prosecution of the work under this contract. Construct with suitable grades and widths; sharp curves, blind corners, and dangerous cross traffic are to be avoided. Provide necessary lighting, signs, barricades, and distinctive markings for the safe movement of traffic. The method of dust control, although optional, must be adequate to ensure safe operation at all times. Location, grade, width, and alignment of construction and hauling roads are subject to approval by the Contracting Officer. Lighting must be adequate to assure full and clear visibility for full width of haul road and work areas during any night work operations.

2.1.2 Barricades

Erect and maintain temporary barricades to limit public access to hazardous areas. Whenever safe public access to paved areas such as roads, parking areas or sidewalks is prevented by construction activities or as otherwise necessary to ensure the safety of both pedestrian and vehicular traffic barricades will be required. Securely place barricades clearly visible with adequate illumination to provide sufficient visual warning of the hazard during both day and night.

2.1.3 Fencing

Provide fencing along the construction site at all open excavations and tunnels to control access by unauthorized people.

a. The safety fencing must be a high visibility orange colored, high density polyethylene grid or approved equal, a minimum of 1.2 m (48 inches) high and maximum mesh size of 50 mm (2 inches), supported and tightly secured to steel posts located on maximum 3 m (10 foot) centers, constructed at the approved location. Install fencing to be able to restrain a force of at least 114.00 kg (250 pounds) against it.

2.2 TEMPORARY WIRING

Provide temporary wiring in accordance with NFPA 241 and NFPA 70. The Contractor is required to conduct frequent inspections of all installed equipment and apparatus and report this on the daily report.

Part 3 Execution

3.1 EMPLOYEE PARKING

Contractor employees will park privately owned vehicles in an area designated by the Project Manager. This area will be within reasonable walking distance of the construction site. Contractor employee parking must not interfere with existing and established parking requirements of the SDSTA installation.

3.2 AVAILABILTIY AND USE OF UTILITY SERVICES

3.2.1 Temporary Utilities

Provide temporary utilities required for construction. Materials may be new or used, must beadequate for the required usage, not create unsafe conditions, and not violate applicable codes and standards.

3.2.2 Sanitation

Provide and maintain within the construction area minimum field-type sanitary facilities approved by the Project Manager and periodically empty wastes into a municipal, district, or station sanitary sewage system, or remove waste to a commercial facility. Obtain approval from the system owner prior to discharge into any district or commercial sanitary sewer system. Any penalties and/or fines associated with improper discharge will be the responsibility of the Contractor. Coordinate with the Project Manager and follow sanitary district regulations and procedures when discharging into the sanitary sewer system. Maintain these conveniences at all times without nuisance.

Include provisions for pest control and elimination of odors. SDSTA toilet facilities will not be available to Contractor's personnel.

3.2.3 Fire Protection

Provide temporary fire protection equipment for the protection of personnel and property during construction. Remove debris and flammable materials daily to minimize potential hazards.

3.3 TRAFFIC PROVISIONS

3.3.1 Maintenance of Traffic

a. Conduct operations in a manner that will not close any thoroughfare or interfere in any way with traffic except with written permission of the Project Manager at least 15 calendar days prior to the proposed modification date and provide a Traffic Control Plan detailing the proposed controls to traffic movement for approval. Contractor may move oversized and slow-moving vehicles to the worksite provided requirements of the highway authority have been met.

b. Conduct work so as to minimize obstruction of traffic and maintain traffic on at least half of the roadway width at all times. Obtain approval from the Contracting Officer prior to starting any activity that will obstruct traffic.

3.3.2 Protection of Traffic

Maintain and protect traffic on all affected roads during the construction period except as otherwise specifically directed by the Project Manager. Measures for the protection and diversion of traffic, including the provision of watchmen and flagmen, erection of barricades, placing of lights around and in front of equipment the work, and the erection and maintenance of adequate warning, danger, and direction signs, will be as required by the State and local authorities having jurisdiction. Protect the traveling public from damage to person and property. Minimize the interference with public traffic on roads selected for hauling material to and from the site. Investigate the adequacy of existing roads and their allowable load limit. Contractor is responsible for the repair of any damage to roads caused by construction operations.

3.3.3 Dust Control

Dust control methods and procedures must be approved by the Project Manager. Treat dust abatement on access roads with applications of calcium chloride, water sprinklers, or similar methods or treatment.

3.4 CONTRACTOR'S TEMPORARY FACILITIES

3.4.1 Administrative Field Offices

Provide and maintain administrative field office facilities within the construction area at the designated site. SDSTA office and warehouse facilities will not be available to the Contractor's personnel.

3.4.2 Appearance of Temporary Facilities

- a. Trailers utilized by the Contractor for administrative or material storage purposes must present a clean and neat exterior appearance and be in a state of good repair.
- b. Keep fencing in a state of good repair and proper alignment. Grassed or unpaved areas, which are not established roadways, will be covered with a layer of gravel as necessary to prevent rutting and the tracking of mud onto paved or established roadways, should the Contractor elect to traverse them with construction equipment or other vehicles; gravel gradation will be at the Contractor's discretion. Mow and maintain grass located within the boundaries of the construction site for the duration of the project.

3.4.3 Security Provisions

Provide adequate outside security lighting at the Contractor's temporary facilities. The Contractor will be responsible for the security of its own equipment.

3.5 CLEANUP

Remove construction debris, waste materials, packaging material and the like from the work site daily. Any dirt or mud which is tracked onto paved or surfaced roadways must be cleaned away. Store any salvageable materials resulting from demolition activities within the fenced area described above or at the supplemental storage area. Neatly stack stored materials not in trailers, whether new or salvaged.

3.6 RESTORATION OF STORAGE AREA

Upon completion of the project remove the bulletin board, signs, barricades, haul roads, and any other temporary products from the site. After removal of trailers, materials, and equipment from within the fenced area, remove the fence that will become the property of the Contractor. Restore areas used by the Contractor for the storage of equipment or material, or other use to the original or better condition. Remove gravel used to traverse grassed areas and restore the area to its original condition, including topsoil and seeding as necessary.

--- End of Section ---

CLOSEOUT SUBMITTALS**Part 1 General****1.1 DEFINITIONS****1.1.1 As-Built Drawings**

As-built drawings are developed and maintained by the Contractor and depict actual conditions, including deviations from the Contract Documents. These deviations and additions may result from coordination required by, but not limited to: contract modifications; official responses to Contractor submitted Requests for Information; direction from the Contracting Officer; designs which are the responsibility of the Contractor, and differing site conditions. Maintain the as-builts throughout construction as red-lined hard copies on site. These files serve as the basis for the creation of the record drawings.

1.1.2 Record Drawings

The record drawings are the final compilation of actual conditions reflected in the as-built drawings.

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

Product Data

Spare Parts Data

Manufacturer's Instructions

Posted Instructions

As-Built Drawings

2.1 AS-BUILT DRAWINGS**2.1.1 Markup Guidelines**

Make comments and markup the drawings complete without reference to letters, memos, or materials that are not part of the As-Built drawing. Show what was changed, how it was changed, where item(s) were relocated and change related details. These working as-built markup prints must be neat, legible and accurate as follows:

a. Use base colors of red, green, and blue. Color code for changes as follows:

(1) Special (Blue) - Items requiring special information, coordination, or special detailing or detailing notes.

(2) Deletions (Red) - Over-strike deleted graphic items (lines), lettering in notes and leaders.

(3) Additions (Green) - Added items, lettering in notes and leaders.

2.1.2 As-Built Drawings Content

Show on the as-built drawings, but not limited to, the following information:

- a. The actual location, kinds and sizes of all sub-surface utility lines. In order that the location of these lines and appurtenances may be determined in the event the surface openings or indicators become covered over or obscured, show by offset dimensions to two permanently fixed surface features the end of each run including each change in direction on the record drawings. Locate valves, splice boxes and similar appurtenances by dimensioning along the utility run from a reference point. Also record the average depth below the surface of each run.
- b. The location and dimensions of any changes within the building structure.
- c. Layout and schematic drawings of electrical circuits and piping.
- d. Correct grade, elevations, cross section, or alignment of roads, earthwork, structures or utilities if any changes were made from contract plans.
- e. Changes in details of design or additional information obtained from working drawings specified to be prepared and/or furnished by the Contractor; including but not limited to shop drawings, fabrication, erection, installation plans and placing details, pipe sizes, insulation material, dimensions of equipment foundations, etc.
- f. The topography, invert elevations and grades of drainage installed or affected as part of the project construction.
- g. Where contract drawings or specifications present options, show only the option selected for construction on the working as-built markup drawings.
- h. Systems designed or enhanced by the Contractor, such as HVAC controls, fire alarm, fire sprinkler, and irrigation systems.
- i. Actual location of anchors, construction and control joints, etc., in concrete.
- j. Unusual or uncharted obstructions that are encountered in the contract work area during construction.

2.2 CLEANUP

Leave premises "broom clean." Clean interior and exterior glass surfaces exposed to view; remove temporary labels, stains and foreign substances; polish transparent and glossy surfaces; vacuum carpeted and soft surfaces. Clean equipment and fixtures to a sanitary condition. Replace filters of operating equipment. Clean debris from roofs, gutters, downspouts and drainage systems. Sweep paved areas and rake clean landscaped areas. Remove waste and surplus materials, rubbish and construction facilities from the site.

--- End of Section ---

OPERATION AND MAINTENANCE DATA**Part 1 General****1.1 SUBMITTALS**

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

Operation and Maintenance Data

Training Plan

1.2 OPERATION AND MAINTENANCE DATA

Submit Operation and Maintenance (O&M) Data for the provided equipment, product, or system, defining the importance of system interactions, troubleshooting, and long-term preventive operation and maintenance. Compile, prepare, and aggregate O&M data to include clarifying and updating the original sequences of operation to as-built conditions. Organize and present information in sufficient detail to clearly explain O&M requirements at the system, equipment, component, and subassembly level. Include an index preceding each submittal.

1.2.1 Package Quality

Documents must be fully legible. Operation and Maintenance data must be consistent with the manufacturer's standard brochures, schematics, printed instructions, general operating procedures, and safety precautions.

1.3 OPERATION AND MAINTENANCE MANUAL FILE FORMAT

Assemble data packages into electronic Operation and Maintenance Manuals. Assemble each manual into a composite electronically indexed file using the most current version of Adobe Acrobat or similar software capable of producing PDF file format. Include a complete electronically linked operation and maintenance directory.

1.3.1 O&M MANUAL LABEL REQUIREMENTS

Provide the following information on the label:

- a. Building Number
- b. Project Title
- c. Activity and Location
- d. Construction Contract Number
- e. Prepared By: (Name, title, phone number and email address)
- f. Date

1.4 TYPES OF INFORMATION REQUIRED IN O&M DATA PACKAGES

The following are a detailed description of the data package items required.

1.4.1 Operating Instructions

Provide specific instructions, procedures, and illustrations for the following phases of operation for the installed model and features of each system:

1.4.1.1 Safety Precautions and Hazards

List personnel hazards and equipment or product safety precautions for operating conditions. List all residual hazards identified in the Activity Hazard Analysis provided under Section 01 35 26 SDSTA SAFETY REQUIREMENTS. Provide recommended safeguards for each identified hazard.

1.4.1.2 Operator Prestart

Provide procedures required to install, set up, and prepare each system for use.

1.4.1.3 Startup, Shutdown and Post-Shutdown Procedures

Provide narrative description for Startup, Shutdown and Post-shutdown operating procedures including the control sequence for each procedure.

1.4.1.4 Normal Operations

Provide Control Diagrams with data to explain operation and control of systems and specific equipment. Provide narrative description of Normal Operating Procedures.

1.4.1.5 Emergency Operations

Provide Emergency Procedures for equipment malfunctions to permit a short period of continued operation or to shut down the equipment to prevent further damage to systems and equipment. Provide Emergency Shutdown Instructions for fire, explosion, spills, or other foreseeable contingencies. Provide guidance and procedures for emergency operation of utility systems including required valve positions, valve locations and zones or portions of systems controlled.

1.4.1.6 Operator Service Requirements

Provide instructions for services to be performed by the operator such as lubrication, adjustment, inspection, and recording gauge readings.

1.4.1.7 Environmental Conditions

Provide a list of Environmental Conditions (temperature, humidity, and other relevant data) that are best suited for the operation of each product, component or system. Describe conditions under which the item equipment should not be allowed to run.

1.4.2 Preventive Maintenance

Provide the following information for preventive and scheduled maintenance to minimize repairs for the installed model and features of each system. Include potential environmental and indoor air quality impacts of recommended maintenance procedures and materials.

1.4.2.1 Lubrication Data

Include the following preventive maintenance lubrication data, in addition to instructions for lubrication required under paragraph OPERATOR SERVICE REQUIREMENTS:

- a. A table showing recommended lubricants for specific temperature ranges and applications.
- b. Charts with a schematic diagram of the equipment showing lubrication points, recommended types and grades of lubricants, and capacities.
- c. A lubrication schedule showing service interval frequency.

1.4.2.2 Preventive Maintenance Plan, Schedule, and Procedures

Provide manufacturer's schedule for routine preventive maintenance, inspections, condition monitoring (predictive tests) and adjustments required to ensure proper and economical operation and to minimize repairs. Provide instructions stating when the systems should be retested. Provide manufacturer's projection of preventive maintenance work-hours on a daily, weekly, monthly, and annual basis including craft requirements by type of craft. For periodic calibrations, provide manufacturer's specified frequency and procedures for each separate operation.

1.4.3 a. Appendices

Provide information required below and information not specified in the preceding paragraphs but pertinent to the maintenance or operation of the product or equipment. Include the following:

1.4.3.1 Parts Identification

Provide identification and coverage for the parts of each component, assembly, subassembly, and accessory of the end items subject to replacement.

1.4.3.2 Warranty Information

List and explain the various warranties and clearly identify the servicing and technical precautions prescribed by the manufacturers or contract documents in order to keep warranties in force. Include warranty information for primary components of the system.

1.4.3.3 Personnel Training Requirements

Provide information available from the manufacturers that is needed for use in training designated personnel to properly operate and maintain the equipment and systems.

1.4.3.4 Testing Equipment and Special Tool Information

Include information on test equipment required to perform specified tests and on special tools needed for the operation, maintenance, and repair of components. Provide final set points.

Part 2 Products

Not Used

Part 3 Execution**3.1 TRAINING**

Prior to acceptance of the facility for Beneficial Occupancy, provide comprehensive training for the systems and equipment specified in the technical specifications. The training must be targeted for the building maintenance personnel, and applicable building occupants. Training must include classroom or field lectures based on the system operating requirements. The location of classroom training requires approval by the Project Manager.

3.1.1 Training Content

The core of this training must be based on manufacturer's recommendations and the operation and maintenance information. The QC Manager is responsible for overseeing and approving the content and adequacy of the training. Include the following for each system training presentation:

- a. Start-up, normal operation, shutdown, unoccupied operation, seasonal changeover, manual operation, controls set-up and programming, troubleshooting, and alarms.
- b. Relevant health and safety issues.
- c. Discussion of how the feature or system is environmentally responsive. Advise adjustments and optimizing methods for energy conservation.
- d. Design intent.
- e. Use of O&M Manual Files.
- f. Review of control drawings and schematics.
- g. Interactions with other systems.
- h. Special maintenance and replacement sources.
- i. Tenant interaction issues.

--- End of Section ---

SECTION 33 11 00**WATER DISTRIBUTION PIPING****PART 1 GENERAL****1.1 SUBMITTALS**

SDSTA approval is required for submittals. Submit the following in accordance with Division 1 Guide Specification Section SUBMITTAL PROCEDURES:

SD-03 Product Data

Pipe, Fittings, Joints and Couplings

Valves

Valve Boxes

SD-07 Certificates

Pipe, Fittings, Joints and Couplings

Valves

SD-08 Manufacturer's Instructions

Manufacturer's Instructions

1.2 DELIVERY, STORAGE, AND HANDLING**1.2.1 Delivery and Storage**

Inspect materials delivered to site for damage. Unload and store with minimum handling and in accordance with manufacturer's instructions. Store materials on site in enclosures or under protective covering. Store plastic piping, jointing materials and rubber gaskets under cover out of direct sunlight. Do not store materials directly on the ground. Keep inside of pipes, fittings, valves, and other accessories free of dirt and debris.

1.2.2 Handling

Handle pipe, fittings, valves, and other accessories in accordance with manufacturer's instructions and in a manner to ensure delivery to the trench or surface location in sound undamaged condition. Avoid injury to coatings and linings on pipe and fittings; make repairs if coatings or linings are damaged. Do not place other material, hooks, or pipe inside a pipe or fitting after the coating has been applied. Inspect the pipe for defects before installation. Carry, do not drag, pipe to the trench or surface location. Use of pinch bars and tongs for aligning or turning pipe will be permitted only on the bare ends of the pipe. Clean the interior of pipe and accessories of foreign matter before being lowered into the trench and keep them clean during laying operations by plugging. Replace material found to be defective before or after laying with sound material without additional expense to the Government. Store rubber gaskets that are not to be installed immediately, under cover out of direct sunlight.

PART 2 PRODUCTS
Not Used

PART 3 EXECUTION

3.1 PRECAUTIONS

3.1.1 Connections to Existing System

Notify SDSTA on the schedule for all piping connections to the existing system so that these connections can be witnessed by WWTP O&M personnel.

3.1.2 Operation of Existing Valves

Do not operate valves within or directly connected to the existing water system without expressed permission from SDSTA.

3.2 INSTALLATION OF PIPELINES

3.2.1 General Requirements for Installation of Pipelines

Submit manufacturer's instructions for pipeline installations. These manufacturer's instructions apply to all pipeline installation except as noted herein.

3.2.1.1 Location of Water Lines

3.2.1.1.1 Water Piping Installation Parallel with Sewer Piping

a. Normal Conditions: Lay water piping at least 10 feet horizontally from a sewer or sewer manhole whenever possible. Measure the distance edge-to-edge. Provide at least 18 inches above the top (crown) of the sewer piping and the bottom (invert) of the water piping.

3.2.1.1.2 Installation of Water Piping Crossing Sewer Piping

a. Normal Conditions: Provide a separation of at least 18 inches between the bottom of the water piping and the top of the sewer piping in cases where water piping crosses above sewer piping.

3.2.1.1.3 Sewer Piping or Sewer Manholes

No water piping is to pass through or come in contact with any part of a sewer manhole.

3.2.1.2 Pipe Laying and Jointing

Remove fins and burrs from pipe and fittings. Before placing in position, clean pipe, fittings, valves, and accessories, and maintain in a clean condition. Provide proper facilities for lowering sections of pipe into trenches. Under no circumstances is it permissible to drop or dump pipe, fittings, valves, or other water line material into trenches. Cut pipe cleanly, squarely, and accurately to the length established at the site and work into place without springing or forcing. Replace a pipe or fitting that does not allow sufficient space for installation of jointing material. Grade the pipeline in straight lines; avoid the formation of dips and low

points. Support pipe at the design elevation and grade. Secure firm, uniform support. Wood support blocking is not permitted. Lay pipe so that the full length of each section of pipe and each fitting rests solidly on the pipe bedding; excavate recesses to accommodate bells, joints, and couplings. Provide anchors and supports for fastening work into place. Make provision for expansion and contraction of pipelines. Keep trenches free of water until joints have been assembled. At the end of each workday, close open ends of pipe temporarily with wood blocks or bulkheads. Do not lay pipe when conditions of trench or weather prevent installation.

3.2.1.3 Connections to Existing Water Lines

Make connections to existing water lines after coordination with WWTP O&M personnel and with a minimum interruption of service on the existing line. Make connections to existing lines under pressure in accordance with the recommended procedures of the manufacturer of the pipe being tapped and as indicated.

3.3 FIELD QUALITY CONTROL

3.3.1 Field Tests and Inspections

Notify the Project Manager a minimum of two days in advance of field testing. Perform field tests and provide labor, equipment, and incidentals required for testing. Provide documentation that all items of work have been constructed in accordance with the contract documents. Do not begin testing on any section of a pipeline where concrete thrust blocks have been provided until at least five days after placing of the concrete.

3.3.2 Leakage Testing

For leakage test, use a hydrostatic pressure not less than the maximum working pressure of the system. Leakage test may be performed at the same time and at the same test pressure as the pressure test. No leakage will be allowed at pipe joints.

3.4 CLEANUP

Upon completion of the installation of water lines and appurtenances, remove all debris and surplus materials resulting from the work.

-- End of Section --